

Govt. Of Assam
Office of the Chief Engineer :: Irrigation Department :: Assam :: Chandmari :: Guwahati-3
(Mechanical Branch)

Memo No. CEI(Mech) 9 / 2019 / 16

Dated Guwahati the 13th March, 2024


ADDENDUM

The Addendum are made for the Sor (Mechanical Works) for the year 2023-24 for Part-II (LIS) from this end which may be read as follows :

Sl. No.	Item	Unit	Rate/ Unit (in Rs)
2.19	Laying, fitting, fixing & connection of Flexible rubber Hose Pipe of size, 250 mm nominal dia. in the delivery line with necessary pipe jointing sets, nuts & bolts, washer, etc. for each pump set maintaining proper alignment as per practical site condition complete as directed. The whole assembly must be leak proof. All materials used for the purpose should be of best quality having relevant IS Specification.	Rm	4643.96 (Rupees four thousand six hundred forty three & paise ninety six) only
2.20	Laying, fitting, fixing & connection of MS/ ERW/ DI Pipe with both ends flanged having drilled as per BSS No. 10, Part-1, Table-D of size, 250 mm nominal dia. in the suction/ delivery line with necessary flange, pipe jointing sets, nuts & bolts, washer, etc. for each pump set maintaining proper alignment as per practical site condition including painting complete as directed. The whole assembly should be leak proof and have good surface finished. All materials used for the purpose should be of best quality having relevant IS Specification. Necessary pipe supports wherever required would be measured as extra.	Rm	5482.28 (Rupees five thousand four hundred eighty two & paise twenty eight) only

APPROVED BY :-


Chief Engineer
Irrigation Deptt.
Assam, Chandmari, Guwahati-03
13/03/2024


Additional Chief Engineer (Mechanical)
Irrigation Department, Assam
Chandmari, Guwahati-3